



Agenda

Introduction

- Purpose
- Context

ARDP

- Overview
- Assumptions

Interim Outputs

- Decade 1
- Decade 2
- Decade 3

Summary & Conclusions

- Summary
- Emerging Conclusions

Purpose

- To provide an overview of the Auckland Rail Development Programme (ARDP)
- To inform the Auckland Transport Alignment Process (ATAP) of the interim outputs of this programme



The Role of Rail

- Every week in Auckland
 - 300,000 journeys are made by rail
 - 3100 passenger services operate
 - 78,000kms are travelled by passenger trains
 - 370,000 tonnes of freight are shifted by rail
- High capacity spine of Auckland's Rapid
 Transit Network (RTN) in the South and West
- Connects Auckland to other cities and ports as an alternative to road freight
- Auckland has committed to investment in rail rapid transit and is now seeing the benefits.









- Britomart Station (2003)
- Rail Development Plan 2006
 - Investment pathway for 10min services and 16m pax p.a
- DART and AEP



- c.\$1.1bn invested in track, electrification, re-signalling, stations
- c.\$500m invested in new rolling stock and depot
- Refurbished DMUs and SA's replaced by new EMUs this year.







More

- Capacity
- Services
- Trains
- Efficient

Better

- Performance
- For the environment
- Stations
- Safety


















What Have We Achieved






What Have We Achieved




Net Tonnes






What Next for Rail

Supporting Auckland's Growth





Current Constraints





Agenda

Introduction

- Purpose
- Context

ARDP

- Overview
- Assumptions

Interim Outputs

- Decade 1
- Decade 2
- Decade 3

Summary & Conclusions

- Summary
- Emerging Conclusions




Auckland Rail Development Programme (ARDP)

- Joint AT/KR initiative
- Output
 - Update of existing Rail Development Implementation Pathway (2014)
 - Agreed, prioritised programme of investment Master Plan for Auckland Rail based on defined service levels
- Milestones
 - End 2015 Interim output for ATAP
 - July 2016 Updated output (Phase 1)
 - FY17 3rd Main construction + resilience works
 - FY18 ARDP construction start



Phased approach





Work Undertaken to Date

- Review of existing network capacity and short term improvements
- Review of infrastructure requirements required to accommodate forecast freight and passenger demand
- Review of wider network infrastructure required to deliver proposed service patterns
- Development / refinement of concept designs and cost estimates focus on works required within the next decade
- Further testing of infrastructure in OpenTrack simulation model
- Development of longer term 'Master Plan' alignment designs for key constraint areas (Westfield, Quay Park, Wiri, Newmarket)
- Refinement of alignment designs to future proof for possible 3rd and 4th Main Lines (NIMT).



Assumptions

- All stops 10 min peak / 15 min off peak passenger service.
- CRL proposed service patterns
- CRL high growth patronage forecasts
- KR / NFDS freight forecasts (limited information available)
- NAL to Northland remains open but no growth




Service Assumptions

Decade 1 FY 2016 – 2025	Decade 2 FY2026 – 2035	Decade 3 FY2036 - 2045
15 Minute Off Peak and Weekend Services (7am – 7pm)	Papakura – Pukekohe Electric Services	Increased frequency of services to accommodate growth – Peak Overlays run for more of the peak
10 Minute 'Clockface' Service (South)	Increased frequency of passenger services to accommodate growth – Peak Overlays in part of peak	Additional service from West to East added (Mt Albert to Glen Innes assumed)
CRL Services	Growth in freight services	Limited additional growth in freight services
Growth in freight services (double weekly shuttles)		



Service Assumptions





Caveats and Exclusions

- Network Extensions excluded may change timing of, or require additional, infrastructure. (South, North West, Airport, etc, Inter-Regional)
- Sensitivity Testing not in scope changes to underlying assumptions (growth, operating patterns, r/s capability) may have material impact on conclusions reached
- Trade Offs Potential trade offs between passenger and freight services not yet examined
- Journey times short term improvements, including reduced dwell times assumed. Pathway for achieving these yet to be confirmed.
- Interim outputs only further work required to confirm detailed investment pathway



Agenda

Introduction

- Purpose
- Context

ARDP

- Overview
- Assumptions

Interim Outputs


- Decade 1
- Decade 2
- Decade 3

Summary & Conclusions


- Summary
- Conclusions



Interim Outputs




Decade 1 FY16 – FY25








2016 Services







2025 Services








Decade 1 Overview

- Short Term Resilience works incl. currently deferred renewals
- Deliver an integrated network control centre (NRCC)
- Complete 3rd Main Wiri-Westfield
- Implement 10min clockface and 15min off-peak timetable
- Improve freight access at POAL, Wiri and Westfield
- More efficient handling of longer freight shuttles
- Remove some level crossings (closure / grade separation)
- Upgrade Onehunga Branch Line for 3tph / 6-Car trains
- CRL works completed and services commence (March 2023)
- Procure c.21 3-Car EMUs for growth & expand Strand stabling
- Rail patronage forecast c.30m p.a. by 2025 (15.4m at Dec 2016)





Decade 1







Short Term Improvements

A programme of immediate capital investment to improve service resilience and performance


- Subject to funding availability
- Excludes concurrent programme of operational improvements

Priority elements include:

Funding current renewals shortfall

Other elements include:

- Wiring of sidings (resilience)
- Signal interlocking changes / Vector curves
- Sarawia St level crossing closure
- Pedestrian crossing safety upgrades
- Long distance facilities at the Strand








Infrastructure Capacity

Additional infrastructure to address key constraints

- 3rd Main Wiri Westfield (incl Wiri POAL)
- Westfield Jcn
- CRL main works (tunnel and connections)
- Henderson, Newmarket, Otahuhu, Britomart, Strand, 3rd Traction Power Feed.
- Onehunga Branch Line upgrade
- Onehunga Branch Line works uncertain pending Airport rail decision – min required for 3tph-6car.
- A robust 15min Off Peak / 10 min even interval passenger service requires further capacity.
- Reduction in spend may require compromise to passenger or freight services (or both)








Freight Efficiency and Growth

Enabling longer freight trains and improved access to Port/Yards for growth.

- Westfield, Otahuhu and Southdown Yards
- POAL Arrival Road
- Freight ETCS fitment

Other operational changes will be required to interwork with intensive metro operations.








Rolling Stock and Stabling

Procurement of new EMUs to accommodate passenger growth

- Timing uncertain patronage driven
- Assumes additional units required this decade
- c.21 3-Car units given minimum practical order
- Sufficient for growth into the 2nd decade, incl.
 Pukekohe electrification
- Linked to need for a 3rd traction power feed
- Additional stabling Strand
- Additional train wash Henderson

Deferral of spend would constrain growth – 3 car trains operating peak services via CRL.








Resilience and Performance

Investment to ensure resilient and reliable network

- Auckland/Northern Control Centre
- Accelerate work to address renewals backlog
- Additional crossovers
- Infill signals and speed improvements
- Additional sidings
- Network electrification sectioning
- Wiri Depot independent feed

Impact of investment renewals programme not yet well developed – new assets must be maintained and renewed.

Existing standards, approaches need review








Level Crossings

Implement policy of removal (grade separation or closure) of all level crossings in electrified area

- More than doubling of train frequencies will exacerbate current issues – safety, delays to road users.
- Assume 5 closures and 5 separations within the decade (in addition to 2 addressed by CRL+ Sarawia St)
- Onehunga branch a particular issue
- Further work required

Existing standards for level crossing protection require review







Level Crossings

Level Crossing		2014	2016	Potential frequency post 2021	Potential frequency post 2031
	Trains per hour peak	8	12	21	26
Morningside Drive	% each hour barrier down	17%	25%	44%	54%
Glenview Road	Trains per hour peak	8	12	21	26
	% each hour barrier down	15%	23%	40%	50%
	Trains per hour peak	15	15	18	18
Manuroa Road	% each hour barrier down	35%	35%	42%	42%
	Trains per hour peak	8	12	21	26
Woodward Road	% each hour barrier down	17%	25%	44%	54%
	Trains per hour peak	8	12	21	26
Bruce McLaren Road	% each hour barrier down	18%	28%	48%	60%
	Trains per hour peak	8	12	21	26
Normanby Road	% each hour barrier down	11%	17%	30%	37%
St Jude Street	Trains per hour peak	8	12	21	26
	% each hour barrier down	16%	23%	41%	51%
Sarawia St	Trains per hour peak	18	28	28	28
	% each hour barrier down	40%	62%	62%	62%






Property

Property purchase will be required in some areas

- Works confined within existing rail corridor where possible
- Retention of rail land in relevant areas essential.
- Competing objectives to sell/develop for commercial gain
- Early protection/acquisition of land may be beneficial
- Placeholder estimate only further design work required. Some costs included within unit rates and not identified separately








Emerging Conclusions

- Total spend dependent on assumptions made and timing of investment
- Compromises / trade offs (passenger, freight, performance, reliability) may reduce or defer capital requirement
- If service enhancements are desired, the identified infrastructure is likely to be required to deliver performance and reliability
- Delivery programme dependent on resources and network access – spend now to reduce disruption later?





Decade 2 FY26 – FY35








Decade 2 Overview


- Electrify Pukekohe to Papakura by 2030
- Construct a 4th Main between Wiri and Westfield to de-conflict Westfield Junction (alternative to grade separation)
- Procure new EMUs for electrification and growth (c.21 x 3-car)
- Additional stabling at Henderson and Pukekohe
- Northern concourse at Newmarket Station in addition to PnR and Station enhancements
- Complete level crossing programme
- Rail patronage forecast to reach c.50m by 2035







2035 Services







Decade 2


Infrastructure Capacity Freight Efficiency Rolling Stock, Maintenance and Stabling Resilience and Performance **Level Crossings** Stations and Interchanges **Property**

- Pukekoke Modifications (capacity and electrification)
- Pukekohe Electrification
- 4th Feed (South)
- · Pukekohe Signal Box removal
- 4th Main Wiri Westfield
- Otahuhu 4th and 5th Platforms (in conjunction with 4th Main)
- Westfield Yard Stage 2 (4x450m roads)
- New EMU (Tranche 3 21x3-Car)
- Pukekohe Stabling (units can be stabled in outstations until complete)
- Henderson Stabling
- Ongoing network renewals
- Assume 10 closures this decade
- Assumed c.13 Grade separations (including as part of Pukekohe Electrification)
- Enhancements, capacity expansion and additional PnR as per ITP
- Newmarket Northern Concourse
- Papakura capacity expansion
- Purchase of property required for the above






Decade 2





Decade 3 FY36 – FY45







Decade 3 Overview


- Demand accommodated by running all peak overlay services as 6-car trains for longer periods
- Additional service from West to East required (making use of full 24tph capacity of CRL and requiring ETCS Level 2)
- Procure c.24 x3-car EMUs
- New maintenance facility and stabling at Henderson
- 4th Platform at Henderson
- Complete 3rd Main to Pukekohe
- Complete 4th Main to Papakura
- Rail patronage forecast to reach c.60m by 2045







2045 Services







Decade 3


Infrastructure Capacity Freight Efficiency Rolling Stock, Maintenance and Stabling Resilience and Performance Level Crossings Stations and Interchanges **Property**

- 3rd Main Wiri Papakura Paerata Pukekohe
- 4th Main Wiri-Papakura
- Henderson 4th Platform
- ETCS Level 2
- Nil identified
- New EMU (Tranche 4 24x3-Car)
- Henderson LMD
- Henderson Stabling
- Ongoing network renewals
- Programme assumed complete
- Enhancements, capacity expansion and additional PnR as per ITP
- Purchase of property required for the above.




Decade 3 (FY36-45)

Decade 3






Summary





Overview 2016 - 2045





Summary Capex (\$m)

Decade 1 (FY16-25)

Decade 2 (FY26-35)

Decade 3 (FY36-45)

Programme	FY2016-2025 \$m	FY2026-2035 \$m	FY2036-2045 \$m
Short Term Programme	29		
Infrastructure Capacity	311	647	682
Freight Efficiency and Growth	74	7	-
Rolling Stock, Stabling and Maintenance	277	246	342
Network Resilience and Performance	179	-	-
Level Crossings	203	382	-
Stations and Interchanges	46	48	18
Property	7	8	60
Total	1,125	1,339	1,102

\$2015 uninflated





Emerging Conclusions

- Investment in capacity and resilience is required – including CRL
- Reduced/deferred spend may be possible with compromises /trade offs – not yet tested
- Programme dependent on network access and resources – make best use of network closures
- Works more disruptive as services and patronage increase
- Level crossings significant issue for road and rail







Thank you.



